



Hi-Fert Storage Shed

Client: Mackay Port Authority

Construction completed: 2008

Construction costs: \$5.5m

The purpose of the fertiliser facility is to receive, warehouse, process and dispatch bulk fertiliser.

The Warehouse has a floor area of approximately 4700m² (60mx67m + covered annexe) and allows for Heavy Vehicle access and egress, facility has a vehicle washdown area with underground tank and oil separator, has electric roller shutter doors, a maintenance shed and office and amenities.

Also Security fencing, stormwater system including Bio-retention pits, Weighbridge.

Construction materials include Colorbond Trimdek Ultra, Hardwood Timber Purlin and Girts and concrete tilt panels up to 7m in height to allow for stacking against walls.

Eave clearance height is 12m to facilitate tipping trucks.

